

OFFICE OF THE  
PROJECT ADMINISTRATOR  
INTEGRATED TRIBAL DEVELOPMENT AGENCY  
RAYAGADA

DETAILED TENDER CALL NOTICE  
WITH SCHEDULE OF QUANTITIES

*Name of Work* : "Construction of Kitchen and Dining Hall at Upper Kodinga Ashram  
School, Kashipur Block"

*Amount put to Tender* : Rs 11,45,721/-

*Amount of bid security* : Rs 11,500/-

*Class of Contractor* : "D" & "C"

*Name of the Tenderer* : .....

*Last Date of receipt of Tender*: 24-09-2019 upto 5.30PM



**BILLS OF QUANTITY**

NAME OF THE WORK:-CONSTRUCTION OF KITCHEN AND DINING HALL AT UPPER KODINGA  
ASHRAM SCHOOL

SL. NO.	ITEMS	QUANTITY	UNIT	RATE	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation trenches & Columns in all kinds of soil within all lead and lifts including dressing the sides, shoring (if necessary), bailing out water and leveling the bed and depositing the excavated materials away from the work site including all costs of labour, sundries, tools & plants required for the work etc. complete as per direction of Engineer-in-Charge.	31.68 Cum.	100 Cum.	18,297.33	5,796.59
2	Filling in foundation and Plinth with sand well watered and rammed & dressed & level to proper gradient including all cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer in Charge.	44.68 Cum.	1 Cum.	676.80	30,240.74
3	Cement concrete (1:4:8) with 4 cm. size hand broken hard granite metals of approved quality including mixing with concrete mixture, lowering & laying in layers not exceeding 300 mm. in depth, ramming compacting to proper thickness, watering, curing for required period including all cost, conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge.	32.61 Cum.	1 Cum.	4,534.96	1,47,866.93
4	9" thick Fly Ash Bricks in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 kg/cm <sup>2</sup> immersing the bricks in water not less than six hours before use in masonry including watering and curing for required period with all cost conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge.				
	<b>Ground Floor</b>	53.80 Cum.	1 Cum.	4,347.15	2,33,887.64
5	Fixing vitrified tiles of Premium grade having thickness of 10mm confirming to IS 13756 of size 600mmx600mm color/printed series(Homogeneous) in floors, treads, steps, landings on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigments to match the shades including cost of glazed tiles of size 0.6m x 0.6m with cost conveyance, royalty, taxes of all materials, labour etc. complete as per the direction of Engineer-in-Charge.				
	<b>Ground Floor</b>	152.50 Sqm.	1 Sqm.	1,015.49	1,54,865.37
6	12 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge.				
	<b>Ground Floor</b>	145.05 Sqm.	1 Sqm.	129.74	18,819.15


CONTRACTOR

*[Handwritten Signature]*  
20.12.19

*[Handwritten Signature]*  
PROJECT ADMINISTRATOR  
I.T.D.A., RAYAGADA

7	16 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge.					
	<b>Ground Floor</b>	180.74	Sqm.	1	Sqm.	33,115.87
8	Labour for fixing of G.C.I Sheet in roof drilling hole in wind ties including fixing of ridges, valleys wind ties etc. excluding cost of fitting.	918.00	Sqm.	1	Sqm.	1,36,786.94
9	Providing, fitting and fixing of M.S paneled doors & windows double leaved shutters with M.S frames made out up the following materials conforming to relevant ISS, ISI frames:- 35 x 35 x 6mm M.S. Angles, shutter style:- Top & Bottom rall 25 x 25 x 3mm M.S Angle, door panel:-1mm CR Sheet. Panel stiffener covering width of each leaf:- 19.50mm, M.S.Flat 3 Nos. on each leaf. Hinges size:- 100mm 6 Nos.(3Nos of each side) but out as per ISS. Hold fast:- 35 x 35 x 6mm M.S Angle 175mm length bifurcated at the tip 3 nos of each side: Handle:19mm M.S Flat 4 nos. fabricated. Aldrop:- 2 nos. bought out as per ISS etc. complete as per the direction of Engineer-in-Charge.					
	<b>Ground Floor</b>	1439.40	Kg	1	Kg	1,03,636.80
10	Labour for fitting and fixing of M.S.Gates, M.S.Door frames, window frames as per approved design etc complete.					
	<b>Ground Floor</b>	33.35	Sqm.	1	Sqm.	9,532.67
11	Painting two coats of Asian/Burger or equivalent synthetic enamel paints over a coat of primer to Iron work after smoothening the surface by sand papering and filling the neat and holes with best quality of putty with cost, conveyance, royalty, taxes of all materials labours etc. complete as per the direction of Engineer-in-Charge.					
	<b>Ground Floor</b>	68.72	Sqm.	1	Sqm.	10,552.36

CONTRACTOR



PROJECT ADMINISTRATOR  
I.T.D.A., RAYAGADA



12	Distemping two coats to walls with distemper of approved shade to give an even shade including cost conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer-in-charge, including the cost of all labour materials etc. complete					
	<b>Ground Floor</b>	180.74	Sqm.	1	Sqm.	109.17      19,730.98
13	Providing & Painting with two coats to the entire outside surface with silicon based weather coat paint of any approved make to the outer surface after scraping and cleaning the surface including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.					
	<b>Ground Floor</b>	145.05	Sqm.	1	Sqm.	120.29      17,448.45
14	Cost of GCI sheet of 0.30mm thick					
	<b>Ground Floor</b>	918.00	Sqm.	1	Sqm.	243.40      2,23,441.20

Total 14 (Fourteen) Nos. items only.

Total cost of Civil work 11,45,721.69

Amount Put to Tender Rs. 11,45,721.00

(Rupees Eleven lakh forty five thousand seven hundred twenty one) only

Rate quoted by the Contractor.....%(both figure and words) less than /Excess Over the amount put to Tender

Signature of the Contractor

Project Administrator,  
I.T.D.A., Rayagada

CONTRACTOR

*Handwritten signature and date: 20/11/19*

PROJECT ADMINISTRATOR  
I.T.D.A., RAYAGADA