

OFFICE OF THE
PROJECT ADMINISTRATOR
INTEGRATED TRIBAL DEVELOPMENT AGENCY
RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SCHEDULE OF QUANTITIES

Name of Work : "Construction of Multi Purpose Community-Cum-Cultural Centre for
the Minority Communities at Rayagada, Rayagada Block"

Amount put to Tender : Rs 13,30,404/-

Amount of bid security : Rs 13,400/-

Class of Contractor : "D" & "C"

Name of the Tenderer :

Last Date of receipt of Tender: 24-09-2019 upto 5.30PM.




BILLS OF QUANTITY

NAME OF THE WORK- CONSTRUCTION OF MULTI PURPOSE COMMUNITY-CUM-CULTURAL CENTRE FOR THE MINORITY COMMUNITIES AT RAYAGADA, RAYAGADA BLOCK

SL. NO.	ITEMS	QUANTITY	UNIT	RATE	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation trenches & Columns in all kinds of soil within all lead and lifts including dressing the sides, shoring (if necessary), bailing out water and leveling the bed and depositing the excavated materials away from the work site including all costs of labour, sundries, tools & plants required for the work etc. complete as per direction of Engineer-in-Charge.	71.28 Cum.	100 Cum.	18,297.33	13,042.34
2	Filling in foundation and Plinth with sand well watered and rammed & dressed & level to proper gradient including all cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer in Charge.	45.36 Cum.	1 Cum.	368.80	16,729.98
3	Cement concrete (1:4:8) with 4 cm. size hand broken hard granite metals of approved quality including mixing with concrete mixture, lowering & laying in layers not exceeding 300 mm. in depth, ramming compacting to proper thickness, watering, curing for required period including all cost, conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge.	47.96 Cum.	1 Cum.	3,444.38	1,65,191.25
4	Reinforced cement concert M-20 grade using 20mm and downgraded size crusher broken hard granite chips of approved quality including mixing with concrete mixture, including hoisting and laying in position & compacting with vibrator to proper design section including all the cost, conveyance, royalty & taxes of all materials, labour, rigid smooth centering, shuttering and dismantling the same after 28 days of casting, watering, curing etc. complete.				
	Ground Floor				
i)	Column Base and Footing	15.60 Cum.	1 Cum.	4,417.89	68,905.50
ii)	Column and Beam	7.81 Cum.	1 Cum.	9,725.60	75,931.14
iii)	Plinth Band	7.32 Cum.	1 Cum.	4,720.92	34,568.49
iv)	Lintel Band	2.11 Cum.	1 Cum.	6,298.48	13,320.34
v)	Roof Slabs	17.48 Cum.	1 Cum.	7,750.46	1,35,464.89
vi)	Chajjas	19.31 Sqm.	1 Sqm.	728.20	14,064.38
5	Supplying HYSD/Tor steel reinforcement from SAIL, VIZAG STEEL OR TATA STEEL brand of required diameter of approved quality including Labour charges for cutting, bending, binding and tying the grills and placing in position including cost, conveyance & taxes of reinforcements confirming to ISI standard and binding wire 18 to 20 gauge and as per drawing, design etc. complete as per the direction of Engineer-in-Charge.				
	Ground Floor	58.93 Qtls.	1 Qtls.	6,770.71	3,63,644.72

CONTRACTOR



 PROJECT ADMINISTRATOR
 I.T.D.A., RAYAGADA
 

6	2.5cm thick grading concrete in C.C. (1:2:2) using 10mm & downgraded crusher broken hard granite chips for roof making proper slope as per requirement on roof including the cost of all labour materials, leak proofing chemicals sico or equivalent as per ISI Code etc. complete as per the direction of Engineer-in-Charge.					
	1st Floor	139.83	Sqm.	1	Sqm.	35,892.98
7	9" thick Fly Ash Bricks in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 kg/cm ² immersing the bricks in water not less than six hours before use in masonry including watering and curing for required period with all cost conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge.					
	Ground Floor	33.07	Cum.	1	Cum.	1,26,320.16
8	Providing, fitting and fixing of M.S paneled doors & windows double leaved shutters with M.S frames made out up the following materials conforming to relevant ISS, ISI frames:- 35 x 35 x 6mm M.S. Angles, shutter style:- Top & Bottom rail 25 x 25 x 3mm M.S Angle, door panel:-1mm CR Sheet. Panel stiffener covering width of each leaf:- 19.50mm, M.S.Flat 3 Nos. on each leaf. Hinges size:- 100mm 6 Nos.(3Nos of each side) but out as per ISS. Hold fast:- 35 x 35 x 6mm M.S Angle 175mm length bifurcated at the tip 3 nos of each side: Handle:19mm M.S Flat 4 nos. fabricated. Aldrop:- 2 nos. bought out as per ISS etc. complete as per the direction of Engineer-in-Charge.(EPM rate)					
	Ground Floor	1093.95	Kg	1	Kg	78,764.40
9	2.5 cm thick A.S. Flooring using 12 mm size black crusher broken hard granite chips in C.C. (1:2:4) with punning, finished smooth with proper slope and thickness, watering, curing for required days with cost conveyance, royalty, taxes of all materials labour etc. complete as per the direction of Engineer-in-Charge.					
	Ground Floor	115.50	Sqm.	1	Sqm.	31,210.69
10	12 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge.					
	Ground Floor	144.22	Sqm.	1	Sqm.	17,634.00
11	16 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge.					
	Ground Floor	299.80	Sqm.	1	Sqm.	52,242.34

CONTRACTOR

Handwritten signature

PROJECT ADMINISTRATOR
I.T.D.A., RAYAGADA

Handwritten signature

12	6 mm thick cement plaster (1:4) over R.C.C works including deep chipping , finished smooth with proper thickness, watering, curing for required days with cost conveyance, royalty, taxes of all materials, labour etc. complete as per the direction of Engineer-in-Charge.					
	Ground Floor	115.50	Sqm.	1	Sqm.	15,773.24
13	Painting two coats of Asian/Burger or equivalent synthetic enamel paints over a coat of primer to Iron work after smoothening the surface by sand papering and filling the neat and holes with best quality of putty with cost, conveyance, royalty, taxes of all materials labours etc. complete as per the direction of Engineer-in-Charge.					
	Ground Floor	60.93	Sqm.	1	Sqm.	7,527.74
14	Primer 1 coat with any approved primers over plastered surface including cost conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer-in-charge, including the cost of all labour materials etc. complete					
	Ground Floor	559.53	Sqm.	1	Sqm.	30,261.31
15	Distempering two coats to walls with distemper of approved shade to give an even shade including cost conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer-in-charge, including the cost of all labour materials etc. complete					
	Ground Floor	415.31	Sqm.	1	Sqm.	24,366.30
16	Providing & Painting with two coats to the entire outside surface with silicon based weather coat paint of any approved make to the outer surface after scraping and cleaning the surface including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.					
	Ground Floor	144.22	Sqm.	1	Sqm.	9,548.59

Total 16 (Sixteen) Nos. items only.

Total cost of Civil work 13,30,404.78

Amount Put to Tender Rs. 13,30,404.00

(Rupees Thirteen lakh thirty thousand four hundred four) only

Rate quoted by the Contractor.....%(both figure and words) less than /Excess Over the amount put to Tender

Signature of the Contractor

Project Administrator,
I.T.D.A.,Rayagada

CONTRACTOR

PROJECT ADMINISTRATOR
I.T.D.A., RAYAGADA